

REF NO.	SHEET NO.	STATION		SIDE	202		601	602	611											SP 1309-1(b)			CALCULATED MJC CHECKED DSN	
					CATCH BASIN REMOVED	PIPE REMOVED 24" AND UNDER	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	CONCRETE MASONRY	24" CONDUIT, TYPE A, 706.02	15" CONDUIT, TYPE B	18" CONDUIT, TYPE B	12" CONDUIT, TYPE C	15" CONDUIT, TYPE C	6" CONDUIT, TYPE F	6" CONDUIT, TYPE F, AS PER PLAN	MANHOLE ADJUSTED TO GRADE (SANITARY)	MANHOLE RECONSTRUCTED TO GRADE (SANITARY)	CATCH BASIN, NO. 2-2B	CATCH BASIN, NO. 2-3	CATCH BASIN, NO. 3A	DATE: JANUARY 2022			BENDS AND BRANCHES FOR INFO. ONLY
																					605	609		
FROM	TO	EACH	FT	CY	CY	FT	FT	FT	FT	FT	FT	FT	FT	EACH	EACH	EACH	EACH	EACH	FT	FT	NO.			
C-1	31-32,34	362+00	373+00	Rt																				
C-2	31-32	362+00	366+93	Lt																	1100			
C-3	32,34	367+37	371+67	Lt																	532			
																					458			
R-1	31	360+97		Rt	1																			
R-2	31 & 32	365+16	366+30	Rt	1	114																		
R-3	32	366+89	367+33	Rt		44																		
R-4	32	367+28	367+35	Rt		28																		
R-5	32	367+56	368+03	Rt		47																		
R-6	32	368+65	369+13	Rt		48																		
R-7	32	369+46	370+50	Rt		104																		
R-8	32 & 34	370+83	372+00	Rt	1	117																		
D-1	31 & 55	362+35		Lt & Rt			2	0.9	24															
D-2	31	365+15		Rt							22									1				
D-3	31	365+15	365+50	Rt								35				1								
D-4	31	365+50	365+80	Rt								30					1							
D-5	31 & 32	365+80	366+50	Rt						70							1							
D-6	32	366+42	366+62	Lt								80								1				
D-7	32	366+50		Rt								15								1				
D-8	32	366+50	367+47	Rt									97							1				
D-9	32	367+27	367+47	Rt										25								1		
D-10	32	367+47	368+50	Rt									103							1				
D-11	32	368+50		Rt									15							1				
D-12	32	368+50	369+32	Rt									82							1				
D-13	32	369+32	369+98	Rt									66							1				
D-14	32	369+98		Rt										15							1			
D-15	32	369+98	370+70	Rt									72							1				
D-16	32	370+70	371+45	Rt									75							1				
S-1	31 & 55	362+55		Rt																				
S-2	32 & 57	366+36		Rt																				
S-3	32 & 57	369+40		Rt											1									
U-1	31	362+00	365+15	Rt											10						305	1		
U-2	31 & 32	362+00	366+42	Lt											10						432	1		
U-3	31 & 32	365+20	366+50	Rt											10						120	1		
U-4	32	366+55	368+50	Rt											10						185	1		
U-5	32	368+55	369+98	Rt											10						133	1		
U-6	32	367+55	371+45	Lt											10						382	1		
U-7	32 & 34	370+03	372+00	Rt											10						187	1		
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>					3	502	2	0.9	24	70	495	147	65	25	70	1	2	1	8	5	1744	2090		

ESTIMATED QUANTITIES - STA. 360+50 TO STA 371+50

CLI-67-16.86