REF NO.	SHEET NO.	STATION FROM	STATION TO	SIDE	202 CATCH BASIN REMOVED	202 PIPE REMOVED, 24" AND UNDER	601 ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	602 CONCRETE MASONRY	611 24" CONDUIT, TYPE A, 706.02	611 15" CONDUIT, TYPE B	611 18" CONDUIT, TYPE B	611 12" CONDUIT, TYPE C	611 15" CONDUIT, TYPE C	611 6" CONDUIT, TYPE F	611 6" CONDUIT, TYPE F, AS PER PLAN	611 MANHOLE ADJUSTED TO GRADE (SANITARY)	611 MANHOLE RECONSTRUCTED TO GRADE (SANITARY)	611 CATCH BASIN, NO. 2-2B	611 CATCH BASIN, NO. 2-3	611 CATCH BASIN, NO. 3A	605 4" SHALLOW PIPE UNDERDRAINS	609 COMBINATION CURB AND GUTTER, TYPE 2	BENDS AND BRANCHES FOR INFO. ONLY 6"x45°
					EACH	FT	CY	CY	FT	FT	FT	FT	FT	FT	FT	EACH	EACH	EACH	EACH	EACH	FT	FT	NO.
C-1	31-32,34	362+00	373+00	Rt																		1100	
C-2	31-32	362+00	366+93	Lt																		532	
C-3	32,34	367+37	371+67	Lt																		458	
R-1	31	360+97		Rt	1																		
R-2	31 & 32	365+16	366+30	Rt	1	114																	
R-3	32	366+89	367+33	Rt		44																	
R-4	32	367+28	367+35	Rt		28																	
R-5	32	367+56	368+03	Rt		47																	
R-6	32	368+65	369+13	Rt		48																	
R-7	32	369+46	370+50	Rt		104																	
R-8	32 & 34	370+83	372+00	Rt	1	117																	
D-1	31 & 55	362+35		Lt & Rt			2	0.9	24														
D-2	31	365+15		Rt								22								1			
D-3	31	365+15	365+50	Rt									35					1					
D-4	31	365+50	365+80	Rt									30						1				
D-5	31 & 32	365+80	366+50	Rt						70									1				
D-6	32	366+42	366+62	Lt								80								1			
D-7	32	366+50		Rt								15								1			
D-8	32	366+50	367+47	Rt							97								1				
D-9	32	367+27	367+47	Rt										25									1
D-10	32	367+47	368+50	Rt							103								1				
D-11	32	368+50		Rt								15								1			
D-12	32	368+50	369+32	Rt							82								1				
D-13	32	369+32	369+98	Rt							66								1				
D-14	32	369+98		Rt								15								1			
D-15	32	369+98	370+70	Rt							72								1				
D-16	32	370+70	371+45	Rt							75								1				
S-1	31 & 55	362+55		Rt													1						
S-2	32 & 57	366+36		Rt													1						
S-3	32 & 57	369+40		Rt												1							
U-1	31	362+00	365+15	Rt											10						305		1
U-2	31 & 32	362+00	366+42	Lt											10						432		1
U-3	31 & 32	365+20	366+50	Rt											10						120		1
U-4	32	366+55	368+50	Rt											10						185		1
U-5	32	368+55	369+98	Rt											10						133		1
U-6	32	367+55	371+45	Lt											10						382		1
U-7	32 & 34	370+03	372+00	Rt											10						187		1
TOTALS CARRIED TO GENERAL SUMMARY					3	502	2	0.9	24	70	495	147	65	25	70	1	2	1	8	5	1744	2090	

SP 1309-1(b)

DATE: JULY 2022

CALCULATED MJG

CHECKED DSN

ESTIMATED QUANTITIES - STA. 360+50 TO STA 371+50

CLI-67-16.86