SHEET NO.	REFERENCE NO.	LOCATION	STATION	SIDE	CODE	SIZE (INCHES)	630 SIGN, FLAT SHEET (SQ FT)	ONE WAY SUPPORT, No. 3 POST (FT)	GROUND MOUNTED SUPPORT, No. 3 POST (FT)	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W10x12 (FT)	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION (EACH)	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL (EACH)	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL (EACH)	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND DISPOSAL (EACH)	SIGN ERECTED, EXTRUSHEET (SQ FT)	GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION (EACH)	BREAKAWAY STRUCTURAL BEAM CONNECTION (EACH)
56	S1	℄ Const. S.R. 17	44+91	LT.	M3-1-24	24" x 12"	2.0										
					M1-1-24-2	24" x 24"	4.0										
					M6-1-24	24" x 18"	3.0										
					M2-H7-66	66" x 24"	11.0										
56	S2		40+41	LT.	R1-1-48	48" x 48"	16.0	14.5	13.5								
					R6-1-48	48" x 18"	6.0										
					R5-1-36	36" x 36"	9.0										
					R6-1-48	48" x 18"	6.0										
56	S3		45+60	LT.	R3-H8ba-36	36" x 30"	7.5		12.5								
56	S4		47+80	LT.	D1-H6	192" x 72"				17.5-18.0					96	2	2
56	S5		48+40	RT.	R3-9b-24	24" x 36"	6.0		14								
					R3-H9j-24	24" x 6"	1.0										
56	S6		48+75	LT.	R3-H8dg-36	36" x 30"	7.5		12.5								
56	S7		49+93	LT.	D-3				10								
56	S8		50+05	LT.	R2-1-30	30" x 30"	6.25		12.5								
56	S9		46+20	RT.	M3-2-24	12" x 24"	2.0		14-14								
					M1-5-24-3	24" x 30"	5.0										
56	S10		54+36	RT.	R3-H8dg-36	36" x 30"			7.5								
57	S11		53+00	LT.	M2-1	24" x 12"	2.0		13								
					M1-1-24-2	24" x 24"	4.0										
57	S12		55+56	LT.	R3-H9j-24	24" x 6"	1.0										
					R3-9b-24	24" x 36"	6.0		14								
57	S13		55+56	RT.	R3-H8bh-36	36" x 30"	7.5		12.5								
57	S14		57+25	RT.	R3-H8bh-36	36" x 30"	7.5		12.5								
57	S15		56+89	LT.	M1-5-30-3	30" x 24"	5.0		11								
57	S16		57+72	RT.	D-3				10								
57	S17		58+31	LT.	R2-1-30	30" x 30"	6.25		13.5-13.5								
					R5-H2b-24												
57	S18		58+48	LT.	R2-1-30	30" x 30"	6.25		11								
57	S19		58+65	RT.	R2-1-30	30" x 30"	6.25		13.5-13.5								
					R5-H2b-24												
57	S20		59+47	RT.	R2-1-30	30" x 30"	6.25		13.5-13.5								
					R5-H2b-24												
58	S21		59+25	LT.	R3-H8bh-36	36" x 30"	7.5		12.5								
58	S22		59+38	RT.	M1-5-24-3	30" x 24"	5.0		11								
58	S23	℄ Const. S.R. 17	60+86	LT.	R3-H8bh-36	36" x 30"	7.5		12.5								
56	R1	℄ Const. S.R. 17	44+91	LT.								4	1				
56	R2		40+41	LT.								3	1				
56	R3		47+80	LT.							3			1			
56	R4		47+65	RT.	W6-3							1	1				
56	R5		49+93	LT.								1	1				
56	R6		50+05	LT.								1	1				
56	R7		46+20	RT.								2	1				
56	R8	℄ Const. S.R. 17	54+36	RT.								1	1				
SUBTOTALS							170.25	14.5	311.5	35.5	3	13	7	1	96	2	2
TOTALS CARRIED TO GENERAL SUMMARY							170	15	312	36	3	13	7	1	96	2	2

SIGNING SUBSUMMARY

UNI-17-3.14